

## Aerobic Treatment





## Aerobic Treatment Units (ATU)

Hydraulic loading as per "Regulation 29 and Schedule 9" of the Department of Health for an Eco-tourism accommodation facility/tent site/caravan park bay is 140L per day per person.


- 1 Tent 2 people 140L x 2 = 280L
- 5 tents 10 people 140L x 10 = 1400L
- 10 tents 20 people 140l x 20 = 2800L
- 20 tents 40 people 140L x 40 = 5600L

All units come with pedestrian covers as standard, heavier load classes available on request. Disposal Fields will be dependent on site and soil conditions for individual cases and will be priced accordingly, a generic example of each type will be listed below.

Eco Tent	Unit Required	Agent Cost (AUD) Supply Ex Works
1-5 Tents	O-2NR - 1.8KL	\$9,300.00 +GST
5-10 Tents	2 x O-2NR - 4KL	\$18,590.00 +GST
10-20 Tents	O-2NR - 6KL	\$24,100.00 +GST
20-30 Tents	O-2NR - 10KL	\$33,300.00 +GST

<sup>\*</sup>Prices Indicating April 2023. POA

<sup>\*</sup>Please note Systems become commercial grade from 6KL upwards





## Generic Examples

For sandy soils to suit O-2NR – 1.8KL Only to be used as a guide for information purposes.

#### 1. FLATBED LEACH DRAINS

The flatbed leach drains are supplied with the distribution pipes, sockets, end plugs, 40mm round to square fittings, geotextile cloth and a 2-port automatic diversion valve.

Standard 10m (2 x 5m configuration) Price: \$1,540.00 plus GST supply only Ex works





#### 2. SUBSURFACE DRIP IRRIGATION

For Landscaping Area/Beds – The 150m2 Subsurface Dripper Field (8LPH dripline at 1m spacing – Product Code DF150K) comes as a kit which includes an Arkal disc filter and all required components. Price also includes pump upgrade to accommodate drippers.

Price: \$1050.00 plus GST supply only Ex works





Accordingly as the systems increase in capacity the disposal field will need to increase to allow for the additional loading Please contact Aquarius Wastewater Systems for individual project pricing.

# Aquarius System Proposal

#### **OUR PROPOSAL INCLUDES THE SUPPLY ONLY OF:**

- An Aquarius System in plastic tanks suitable for installation in a non-trafficable area; as well
  as any associated pumps, control panels and fittings as shown on attached drawing. The
  prices quoted above are based on an invert level of the sewer drains entering the Primary
  Tank of the ATU to be 650- 850mm from FGL.
- Supply of Flatbed Leach Drains or Subsurface Drip Irrigation Kit (if selected)

#### **OUR PROPOSAL EXCLUDES:**

- Installation and commissioning
- Delivery of Equipment to Site
- Feeder pipe from ATU to disposal area
- The provision of a concrete pump up tank if required, nor any associated pumps, control panels, fittings, transportation or installation
- Any electrical work

#### INSTALLATION

Aquarius Wastewater Systems is a distributor of ATU's and affiliated products and does not carry out installations. We however can put you in contact with trained agents that can install, service and commission the system for you.

NB: Installation and commissioning to be by a third-party independent contractor, ... That you are required to contract with directly for these services.

#### SERVICE AND MAINTENANCE

As a Department of Health's requirements, the system requires six monthly servicing and needs to be serviced by an AWS approved Service Agent that is registered with the Department of Health WA. For pricing, an accurate quote will need to come from a service agents. Costs vary according to location – estimate \$250.00-350.00 plus GST.

#### **ELECTRICAL / POWER REQUIREMENTS**


Our ATU's Power requirement for systems up to 4KL is single phase, 240-volt, 50 Hz, 20-amp. This is required to be on an independent separate, D circuit breaker, within the distribution board of the house (minimum 2.5 mm cable). For ATU's 6KL and above an independent separate D circuit breaker will also be required however it will need to be a 32-amp rating. Power cable to the ATU control panel is the responsibility of the owner/builder.

#### WARRANTY CONDITIONS

The system must be installed, commissioned and serviced by an AWS approved Installer and Service Agent that is registered with the DoH WA. A copy of the local Council "Permit to Use", signed Service and Maintenance Agreement and completed Warranty Form must be supplied to Aquarius Wastewater Systems upon completion of the job to validate all warranties.



### **Domestic Units**




## Commerical Units

CERTIFICATION

DATE: 22.02.2018 SIGNATURE: 0

PROCESS ENGINEER: Olaf Stams, State Qualified Technician ATST Kiel Germany Environmental Technology/Process Engineering

12.09.18



FOOTPRINT

0

0

0

AQUARIUS 6KL O-2NR ATU

22.02.2018

ECKED



24 Marine Terrace, Fremantle, Western Australia, 6160 +61 8 9193 8007 | ecostructures.com.au

### A company of The WABi Group









